



Basic Details

Organisation Chain	Department of Pharmaceuticals National Institute of Pharmaceutical Education and Research Hajipur		
Tender Reference Number	NIPER-HJP/S and P/2024-25/03		
Tender ID	2024_MCF_754079_1		
Tender Type	Open Tender	Form of contract	Works
Tender Category	Works	No. of Covers	2
Payment Mode	Not Applicable	Is Multi Currency Allowed For BOQ	No
Is Multi Currency Allowed For Fee	No		

Cover Details, No. Of Covers - 2

Cover No	Cover	Document Type	Description
1	Fee/PreQual/Technical	.pdf	As per BoQ (Bill of Quantity) documents
2	Finance	.xls	As per BoQ (Bill of Quantity) documents

Tender Fee Details, [Total Fee in ₹ * - 0.00]

Tender Fee in ₹	0.00	Fee Payable To	NA	Fee Payable At	NA
Tender Fee Exemption Allowed	NA				

EMD Fee Details

EMD Amount in ₹	0.00	EMD Exemption Allowed	NA
EMD Fee Type	NA	EMD Percentage	NA
EMD Payable To	NA	EMD Payable At	NA

Work /Item(s)

Title	NIPER-HJP/S and P/2024-25/03				
Work Description	Bill of Quantity (BoQ) for renovation with painting work of HPLC Lab, Pharmacy practice lab and Lobby at 2nd floor of admin building, NIPER Hajipur.				
Pre Qualification Details	Please refer Tender documents.				
Tender Value in ₹	2,50,000	Product Category	Miscellaneous Works	Sub category	NA
Contract Type	Tender	Bid Validity(Days)	60	Period Of Work(Days)	10
Location	NIPER Hajipur	Pincode	844102	Pre Bid Meeting Place	NA
Pre Bid Meeting Address	NA	Pre Bid Meeting Date	NA	Bid Opening Place	NIPER Hajipur

Critical Dates

Publish Date	22-Apr-2024 05:00 PM	Bid Opening Date	26-Apr-2024 02:00 PM
Document Download / Sale Start Date	22-Apr-2024 05:00 PM	Document Download / Sale End Date	26-Apr-2024 11:00 AM
Clarification Start Date	22-Apr-2024 05:00 PM	Clarification End Date	26-Apr-2024 10:00 AM
Bid Submission Start Date	22-Apr-2024 05:00 PM	Bid Submission End Date	26-Apr-2024 11:00 AM

Tender Documents

NIT Document	S.No	Document Name	Description	Document Size (in KB)
	1	Tendernotice_1.pdf	As per BoQ (Bill of Quantity) documents	984.76

Work Item Documents	S.No	Document Type	Document Name	Description	Document Size (in KB)

1	Tender Documents	NIQ-03.pdf	As per BoQ (Bill of Quantity) documents	984.76
---	------------------	------------	---	--------

Tender Inviting Authority

Name	Registrar I/C, NIPER Hajipur
Address	Registrar I/C, NIPER Hajipur EPIP Campus, Industrial Area, Hajipur - 844102

Tender Creator Details

Created By	Kumar Pankaj
Designation	Finance Officer
Created Date	22-Apr-2024 04:31 PM



राष्ट्रीय औषधीय शिक्षा एवं अनुसंधान संस्थान, हाजीपुर

National Institute of Pharmaceutical Education and Research (NIPER), Hajipur

औषध विभाग / Department of Pharmaceuticals

रसायन एवं उर्वरक मंत्रालय, भारत सरकार / Ministry of Chemicals & Fertilizers, Govt. of India

Ref. No. NIPER-HJP/S&P/2024-25/03

Dt. 22/04/2024

Notice Inviting Quotations

A. **Bill of Quantity (BoQ)** for renovation with painting work of HPLC Lab, Pharmacy practice lab and Lobby at 2nd floor of admin building, NIPER Hajipur.

Sealed Quotations are Invited from the reputed firms as per terms and conditions given below:-

The rates may be given as indicated works below:-

Si No.	Item Description	Quantity	Unit Rate	Total Quoted cost
1.	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. all complete job	2 Nos.		
2.	Demolishing dry brick pitching in floors, drains etc. including stacking of serviceable material and disposal of unserviceable material.	9.30 m ²		
3.	Dismantling tile work in floors laid in cement mortar including disposal of material.	8.50 m ²		
4.	15mm cement plaster mix (1:6).	17.30 m ²		
5.	Providing and applying white cement based putty of approved brand and manufacturer. all complete job	17.30 m ²		
6.	Applying priming coats with water thinnable cement primer on wall surface. all complete job	130 m ²		
7.	Wall painting with acrylic emulsion paint of approved brand and manufacture. all complete job	174.50 m ²		
8.	Half brick masonry with common burnt clay FPS bricks in cm (1:4)	1.40 m ²		
9.	Providing and laying vitrified floor tiles in different size of approved make laid in cm (1:4)	17.10 m ²		
10.	Estimated cost of plumbing material with labour charge (attached in separate sheet) (https://drive.google.com/file/d/1GO3Xr586e-olJXAIZYdg6EYg3wdPIW2B/view?usp=drivesdk)	1 set		

B. Pharmacy Practice

The rates may be given as indicated works below:-

Si No.	Item Description	Quantity	Unit Rate	Total Quoted cost
1.	Applying primer coats with water thinnable cement primer on wall surface.	133.20 m ²		
2.	Wall painting with acrylic emulsion paint of approved brand and manufacture. All complete job	180.50 m ²		

C. Lobby at 2nd floor

The rates may be given as indicated works below:-

Si No.	Item Description	Quantity	Unit Rate	Total Quoted cost
1.	Applying primer coats with water thinable cement primer on wall surface.	80.18 m ²		
2.	Wall painting with acrylic emulsion paint of approved brand and manufacture. All complete job	108 m ²		
Total (A+B+C)				
Total in Word:				

Terms and Condition:-

1. Interested vendors are requested to visit the site and discuss with the indenting Department/Purchase Section for actual scope of work and requirement which may vary from the above listed requirement.
2. Sealed Quotation may be submitted by the vendor latest by 26th April 2024 till 11.00 AM to the tender box of NIPER Hajipur.
3. Quotation should be in the name of the Director, NIPER Hajipur, Vaishali, Bihar-844102.
4. The Quotation must include GST and Delivery/Loading/Unloading Charges. The L1 Price Calculate on Overall Quoted rate for table A, B and C.
5. Vendor should have registered with GST and done at least one similar work.
6. The above works shall be carried out within 10 days from the date of award of work.
7. Actual work may vary.
8. NIPER-Hajipur reserves the right to amend, withdraw or cancel the quotation notice at any point of the bidding process.

Sd/-
Registrar(I/c)

1.	3"	S.W.R	पाईप	—	80 फिट —
2.	3"	"	बैंड	—	5 पीस —
3.	3"	"	टी	—	4 पीस —
4.	3"	"	श्रीकैट	—	5 पीस —
5.	3"	"	डोर बैंड	—	2 पीस —
6.	4" x 3"	"	नहानी ब्राप	—	4 पीस —
7.	P.V.C		श्रीकैट	—	500 ग्राम —
8.	1" U.P.V.C		पाईप	—	120 फिट —
9.	1"	"	श्रीकैट	—	12 पीस —
10.	1"	"	हमपा	—	16 पीस —
11.	1"	"	टी	—	8 पीस —
12.	1" x 1/2"	"	टी	—	5 पीस —
13.	1" x 1/2"	"	श्रीकैट	—	2 पीस —
14.	1"	"	बलव मल्ल	—	1 पीस —
15.	1 1/2"	"	पाईप	—	30 फिट —
16.	1/2"	"	श्रीकैट	—	3 पीस —
17.	1/2"	"	हमपा	—	8 पीस —
18.	1/2"	"	टी	—	5 पीस —
19.	1/2"	"	हमपा बाल	—	5 पीस —
20.	1/2"	"	कलॉम्प	—	15 पीस —
21.			एंगल कॉम्प	—	5 पीस —
22.			कनीसलन पाईप	—	5 पीस —
23.			टेपलॉन टेप	—	5 पीस —
24.			पुरे काम का मजदूरी भाड़ा लक्षित	—	सब तरीकल